Further layer of suitably graded material to be applied where deemed necessary by the site engineer.

1:2 Earthworks

1:2 MAX

EXISTING FALL

EXISTING CONSTRUCTION

Suitably graded capping material up to 400mm thickness material grade to be approved by design engineer prior to commencement on site.

Pell Frischmann
93 GEORGE STREET, EDINBURGH, EH2 3ES

Tel: +44 (0)131 240 1270
Email: pfedinburgh@pellfrischmann.com
www.pellfrischmann.com

Client
SLR

Project
Breezy Hill Energy Project

Drawing Title
Figure 2.6
Typical Existing Road Widening

	Name	Date	Scale		
			NTS @ A1		
Designed	JS	19.02.2025	File 250219 Breezy Hill Construction Details		
Checked	SCM	19.02.2025	Drawing Status DRAFT		

Drawing No. 10109034_006	Revision P1

© Pell Frischmann